

Tramo nº 1 - <Tramo 1>

PK	Excavac	Cama	Rell Exc	Repos
30.13	75.27	10.11	56.06	69.41
60.39	75.57	10.16	56.29	69.69
104.07	108.15	14.66	80.29	100.42
148.29	109.47	14.84	81.27	101.64
235.93	217.83	29.42	161.95	201.64
324.30	219.64	29.66	163.30	203.32
336.89	32.07	4.22	24.05	29.13
347.98	28.27	3.72	21.20	25.68
355.62	19.28	2.56	14.41	17.64
363.76	20.53	2.73	15.35	18.79
371.56	19.92	2.62	14.94	18.07
378.76	18.37	2.42	13.78	16.67
396.24	43.64	5.87	32.49	40.26
413.84	43.94	5.91	32.72	40.54
443.93	75.13	10.10	55.95	69.30
474.08	75.29	10.12	56.07	69.45
510.33	91.28	12.17	68.17	83.66
546.29	90.55	12.07	67.62	82.99
574.53	70.51	9.48	52.51	65.04
602.81	70.62	9.49	52.59	65.14
629.37	65.41	8.92	48.47	60.98
658.16	70.89	9.66	52.54	66.09
700.40	110.25	14.18	83.32	98.32
740.24	104.00	13.37	78.60	92.75
752.14	30.11	4.00	22.52	27.51
763.54	28.82	3.83	21.55	26.33
801.98	95.49	12.90	70.98	88.43
841.20	97.44	13.17	72.43	90.24
885.34	110.69	14.81	82.55	101.76
928.33	107.82	14.43	80.41	99.12
940.21	29.57	3.99	22.00	27.34
953.45	32.98	4.45	24.53	30.49
956.27	6.09	0.95	4.29	6.27
980.94	53.42	8.28	37.68	54.93
1008.15	68.14	9.13	50.79	62.71
1013.89	14.19	1.93	10.53	13.19
1021.33	18.39	2.50	13.65	17.10
1030.95	24.52	3.23	18.39	22.26
1038.24	18.60	2.45	13.95	16.88
1046.71	21.84	2.84	16.45	19.65
1053.40	17.27	2.25	13.00	15.54
1064.82	28.66	3.83	21.37	26.33
1076.05	28.18	3.77	21.02	25.90
1080.06	10.13	1.35	7.57	9.27
1083.42	8.46	1.13	6.33	7.74
1113.37	73.68	10.06	54.58	68.75
1144.26	75.96	10.37	56.27	70.88
1164.17	50.13	6.68	37.43	45.96
1183.64	49.02	6.54	36.60	44.94
1207.49	58.29	8.01	43.08	54.65
1232.24	60.48	8.31	44.70	56.70
1246.94	37.44	4.93	28.07	34.02
1260.85	35.45	4.67	26.57	32.21
1270.29	23.53	3.17	17.51	21.72
1279.92	24.03	3.23	17.89	22.19
1290.81	27.23	3.65	20.29	25.08
1301.66	27.16	3.64	20.23	25.01
1335.24	84.15	11.27	62.74	77.41
1368.68	83.81	11.22	62.49	77.09
1399.47	76.45	10.34	56.82	70.82
1430.79	77.76	10.51	57.80	72.04
1461.46	76.35	10.30	56.79	70.60
1492.85	78.12	10.54	58.11	72.24
1507.52	36.67	4.93	27.32	33.80
1522.02	36.24	4.87	26.99	33.40
1548.60	66.43	8.92	49.48	61.24
1575.05	66.10	8.88	49.23	60.93
1598.95	59.85	8.02	44.62	55.08
1623.23	60.83	8.15	45.34	55.98
1646.50	50.06	6.54	38.61	50.27
1669.44	49.36	6.45	38.07	49.57
1678.50	19.59	2.55	15.13	19.60
1687.76	20.00	2.60	15.45	20.02
1694.87	15.32	2.00	11.82	15.37

PK	Excavac	Cama	Rell Exc	Repos
1701.90	15.13	1.98	11.68	15.19
1711.39	20.54	2.67	15.87	20.53
1721.70	22.32	2.90	17.24	22.32

RESULTADOS DE LA MEDICION

Medición de excavación normal

Medición de cama

Medición de relleno de excavación

Medición de reposición de calzada

4264.13 m³

572.56 m³

3180.76 m³

3951.25 m²

1.50 m - 2.00 m

MEDICION DE POZOS

39 pozos

66.29 m

Sección Nº 10

Sección Nº 11

MEDICION DE TUBERIA

98.573 m

1629.043 m